

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-00312-0000

LEASE NAME Ackerman

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Santa Fe Pipe & Supply, Inc.

SEC. 29 TWP. 24 RGE. 15 (E) or (W)

ADDRESS Box 562, Great Bend, Ks. 67530

COUNTY Stafford

PHONE (316) 792-2169 OPERATORS LICENSE NO. 5540

Date Well Completed 10-19-86

Character of Well oil

Plugging Commenced 5-13-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-29-89

Did you notify the KCC District Office prior to plugging this well? Yes

Which agent did you notify? Duane Rankin

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 4505'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION
 7-7-89
 JUL -7 1989

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	223'	None
				5-1/2"	4300'	2,519.80'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3850' and 5 sacks cement. Shot casing at 3500', 3200', 2800' & 2500'. Pulled 81 joints of 5-1/2" casing. Howco plugged well with 350# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 150# hulls and 120 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 100 psi and shutin 50 psi...

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1989

Iona M. Leatherman
 Notary Public

My Commission Expires
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 7-26-91