


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 36 Twp. 24S Rge. (E) 15 (W)
Location as "NE/CNW&SW&" or footage from lines NE NE SW
Lease Owner Wilkinson Drilling, Inc.,
Lease Name Thurow "A" Well No. 2
Office Address 805 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal
Date well completed March 29, 1960
Application for plugging filed September 11, 1961
Application for plugging approved September 11, 1961
Plugging commenced September 11, 1961
Plugging completed September 11, 1961
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4511 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	271	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5 1/2 Inch casing @ 4510 feet.
Casing collapsed @ 3940 feet w/ cable tools
and overshot in hole. Perf & Squeezed @
1030 feet. Pushed plug to 3940 feet.
Dumped 5 sacks of cement thru bailer.
Pulled 660 feet of 5 1/2 inch. Filled hole
with mud to 240 feet. Bridged and 20 sacks
of cement. Mud to 40 feet; bridged and
capped to base of cellar w/10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
4-22-64
APR 22 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Central Pipe Pullers
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF Sedgewick, ss.
Walter M. Wilkinson (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson
805 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of April, 1964

MAY 1 1966
My commission expires

Notary Public.

WILKINSON DRILLING INCORPORATED

~~WILKINSON DRILLING INCORPORATED~~

WICHITA 2, KANSAS
805 UNION CENTER

May 2, 1960

THUROW "A" #2

Company:	Wilkinson Drilling, Inc.	Location:	NE NE SW Sec. 36-24s-15w
Contractor:	Company Tools		Stafford County, Kansas
Commenced:	March 26, 1960	Elevation:	2011 KB
Completed:	March 29, 1960		2006 GL
Total Depth:	4511'	Casing:	Set 8 5/8" @ 271'

FIGURES INDICATE BOTTOMS OF FORMATIONS:

<u>Depth</u>	<u>Formations</u>
0 - 945	Sand and shale
945 - 970	Anhydrite
970 - 1600	Shale, sand, and lime
1600 - 1800	Shale and lime
1800 - 3634	Lime and shale
3634 - 3750	Shale
3750 - 4140	Lime
4140 - 4182	Shale
4182 - 4218	Chert
4218 - 4277	Shale
4277 - 4370	Chert and dolomite
4370 - 4433	Shale and sand
4433 - 4511	Dolomite

We hereby certify the above and foregoing to be a true and correct copy of the log on the Thurow "A" #2, located in the NE NE SW of Section 36-24s-15w, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson
Walter M. Wilkinson - President

Subscribed and sworn to before me this second day of May, nineteen hundred and sixty.

Carolyn K. Moore
Carolyn K. Moore

My commission expires January 2, 1961.