


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 36 Twp. 24 Rge. 15 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines ~~NE~~ NE SW
Lease Owner Harry Koplin
Lease Name Vic Thuroy Well No. 1
Office Address 153 W. Huron, Chicago 10, Illinois
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-4-51 19
Application for plugging filed 9-4-51 19
Application for plugging approved 9-4-51 19
Plugging commenced 9-4-51 8:00 P.M. 19
Plugging completed 9-4-51 11:55 P.M. 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4470 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud bridged hole 245 feet cemented with 15 sacks bridged hole 35 feet cemented with 10 sacks to top of surface pipe

RECEIVED
RECD
9-20-51 SEP 20 1951
DIVISION

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to
Address

STATE OF ILLINOIS, COUNTY OF COOK, SS.
HARRY KOPLIN, OWNER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry Koplin
153 W. HURON ST., CHICAGO 10, ILL.
(Address)

SUBSCRIBED AND SWORN to before me this 17TH day of SEPTEMBER, 1951
Aldona A. Nayjalis
Notary Public.

My commission expires 6/1/55 23-5091-S 8-50-10M

PLUGGING
FILE SEC-36T 24R(50)
COOK PAGE 104 LINE 6

HARRY KOPLIN
153 W. Huron St.
Chicago 10, Ill.

Throw No. 1
NE SW of Sec. 36-24-15
Stafford County, Kansas
Commenced R. D.: 8/19/51
Completed R. D.: 9/4/51
Total Depth: 4470'
Casing Record: 271' of 8.5/8" Surf. Pipe

Initial Prod: D & A
Elevation:
Contractor: S. A. Berwick
Drilling Co.

Strata	Depth
Sand and Shale	0 - 100'
Shale and Shells	100 - 271
Shale and Clay	271 - 831
Shale and Redbed	831 - 980
Anhydrite	980 - 1020
Shale and Redbed	1020 - 1250
Shale and Shells	1250 - 1945
Shale and Lime	1945 - 3100
Shale	3100 - 3160
Shale and Lime	3160 - 3510
Lime	3510 - 3535
Lime and Shale	3535 - 3725
Lime	3725 - 3788
Lime and Shale	3788 - 3898
Lime	3898 - 4165
Chert and Lime	4165 - 4225
Lime and Shale	4225 - 4282
Chert and Lime	4282 - 4392
Lime and Sand	4392 - 4445
Lime	4445 - 4470

I hereby certify the above a true and correct log as reflected by the daily drilling reports of the S. A. Berwick Drilling Co., Great Bend, Kansas.

S. A. Berwick
Owner

Signed and sworn to in my presence this 7th day of September, 1951,
by S. A. Berwick, owner of the S. A. Berwick Drilling Co.

Clayton Bell
Notary Public

My Commission Expires: 2/16/55

PLUGGING
FILE SEC 8KT 24 R 150
BOOK PAGE 106 LINE 62

RECEIVED
STATE COMMISSION
SEP 22 1951
CONSERVATION DIVISION
Wichita, Kansas