

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 36 Twp. 24 Rge. 15 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SE NW NW  
Lease Owner Specter Pipe & Supply, Inc.

Lease Name Satterlee Well No. 5

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 1-6-61 19

Application for plugging filed June 26, 1972 19

Application for plugging approved June 28, 1972 19

Plugging commenced 7-11-72 19

Plugging completed 7-23-72 19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G.R. Biberstein  
Producing formation Arbuckle Depth to top 4395 Bottom 4397 Total Depth of Well 4402 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	278 ft.	none
				5 1/2" OD	4397 ft.	2300 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 4200 ft. with sand; dumped 5 sacks cement pumped 2 sacks hulls, pumped 15 sacks mud; pumped 100 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
8-7-72  
1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Company  
Address Rt. 4, Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
(Address) [Address]

SUBSCRIBED AND SWORN TO before me this 4th day of August, 1972

My commission expires May 21, 1975

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


COPY

Company- WILKINSON DRILLING, INC.  
 Farm- Satterlee (Twin) No. 5

SEC. 36 T. 24 R.15W  
 SE NW NW

Total Depth. 4402'  
 Comm. 12-26-60 Comp. 1-6-61  
 Shot or Treated.  
 Contractor.  
 Issued. 5-27-61

County Stafford  
 KANSAS



CASING:  
 8 5/8" 278' cem w/280 sx.  
 5" 4397'

Elevation. 2013' KB

Production. 100 BOFD

Figures Indicate Bottom of Formations.

surface soil & sand	145
shale & shells	415
red beds & shale	950
shale & shells	1630
shale & lime	1970
lime & shale	3588
Heebner shale	3594
shale & lime	3628
silty shale & shale	3733
lime & shale	4134
varicolored shale & chert	4158
shale	4190
chert & lime	4316
sandy shale & shale	4348
shale	4382
sand	4393
shale	4396
Arbuckle dolomite	4402
Total Depth	4402

KTD

TOPS: SCOUT	
Heebner	3588
Douglas	3628
Brown Lime	3733
Lansing	3743
Conglomerate	4134
Mississippi	4158
Viola	4190
Simpson	4316
Arbuckle	4395

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 28 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas