


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 36 Twp. 24 Rge. 15^W (X) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW&SW" or footage from lines SW NE SE
Lease Owner WILKINSON DRILLING, INC.
Lease Name PRAEGER Well No. 4
Office Address 805 Union Center Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 11 1960
Application for plugging filed April 11 1960
Application for plugging approved April 11 1960
Plugging commenced April 11 1960
Plugging completed April 11 1960
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4453' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		40	80			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Fill hole with heavy mud, plug @ 240' topped with 1/4 sack of hulls, and 20 sacks cement through drill pipe. Mud to 35', plug, 1/4 sack of hulls, and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
5-17-60
MAY 17 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor WILKINSON DRILLING, INC.
Address 805 Union Center Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Walter M. Wilkinson (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson
805 Union Center Bldg, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of April, 1960

My commission expires January 2, 1961
Carolyn K. Moore
Carolyn K. Moore Notary Public.



WILKINSON DRILLING, INC.
805 Union Center Building
Wichita 2, Kansas

May 1, 1960

PRAEGER #4

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1960
CONSERVATION DIVISION
WICHITA, KANSAS

Company - WILKINSON DRILLING, INC.
Contractor - Company Tools
Commenced - March 30, 1960
Completed - April 11, 1960
Total Depth - 4453'
Location - SW NE SE, Section 36-24^S-15^W,
Stafford County, Kansas
Elevation - 2006' Ground Level
Casing - 8 5/8" @ 280' with 290 sacks

FIGURES INDICATE BOTTOMS OF FORMATIONS

<u>Depth</u>	<u>Formations</u>
0 - 2240	Sand and Shells.
240 - 960	Shale and Shells.
960 - 985	ANHYDRITE.
985 - 2005	Shale and Shells.
2005 - 2330	Lime and Shale.
2330 - 2442	Lime.
2442 - 3616	Lime and Shale.
3616 - 3624	Shale.
3624 - 3628	Limestone.
3628 - 3638	Shale.
3638 - 3658	Limestone.
3658 - 3768	Shale.
3768 - 4176	Lime, Shale Streaks.
4176 - 4270	Vari-colored Shale and Chert.
4270 - 4337	Chert and Shale Streaks.
4337 - 4388	Sandstone and Shale Streaks.
4388 - 4453	ARBUCKLE Dolomite.

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Praeger #4, located in the SW NE SE, Section 36-24^S-15^W, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson

Subscribed and sworn to before me this first day of May, nineteen hundred and sixty.

Carolyn K. Moore

My commission expires January 2, 1961