

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County. Sec. 36 Twp. 24 Rge. 15 (E) W (W)

Location as "NE/CNW&SWK" or footage from lines. NE NW NW
Lease Owner Welch & Olson
Lease Name Satterlee Well No. 4
Office Address 353 Armour, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-5-66 _____ 19____
Plugging completed 10-12-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4402 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	277'	None
				5-1/2"	4397'	2913'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4402', sanded hole to 4375' and dumped 5 sacks of cement @ 4375' with dump bailer. Pulled 5 1/2" casing, set 10' rock bridge @ 270' and dumped 5 sacks of cement. Bailed fluid to top of cement plug and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1966

12-16-66

CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~CONSERVATION DIVISION~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1966

Milton J. Volin
Notary Public.

My commission expires May 20, 1968

WILKINSON DRILLING, INC.

818 EAST TENTH STREET
GREAT BEND, KANSAS

December 31, 1960

Satterlee # 4

Company: WILKINSON DRILLING, INC.
Contractor: Company Tools
Commenced: December 12, 1960
Completed: December 24, 1960
Total Depth: 4402'
Location: NE NW NW, Section 36-24-15
Stafford County, Kansas.
Elevation: 2010 Kelly Bushing
Casing: 8 5/8" @277' W/280 sacks

RECEIVED
STATE CORPORATE TAX COMMISSION
SEP 22 1966
REGISTRATION DIVISION
WARRANTS SECTION

FIGURES INDICATE BOTTOMS OF FORMATION

<u>DEPTH</u>	<u>FORMATION</u>
0 - 281	Shale & Shells
281 - 925	Shale, Shells & Red Beds
925 - 950	ANHYDRITE
950 - 1886	Shale & Shells
1886 - 3576	Lime Shale
3576 - 3585	Heebner Shale
3585 - 3618	Lime & Shale Streaks
3618 - 3721	Shale & Silty Shale
3721 - 4118	Lime & Shale Stringers
4118 - 4143	Varicolored Shale & Chert
4143 - 4189	Shale
4189 - 4316	Chert
4316 - 4338	Shale & Sandy Shale
4338 - 4378	Shale
4378 - 4385	Sand
4385 - 4394	Shale
4394 - 4402	ARBUCKLE

ROTARY TOTAL DEPTH 4402'

PIPE SET 4397- 75 not cont.

We hereby certify the above and foregoing to be a true and correct copy of the log on the Satterlee #4, Located in the NE NW NW, Section 36-24-15, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson

Subscribed and sworn to before me this 31st Day of December, Nineteen hundred and sixty.

Caroleen K. Moore

My Commission expires January 2, 1961