

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-13263-0001

~~XXXXXXXX~~ Docket #C9013

LEASE NAME Thurrow A

WELL NUMBER #3

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 36 TWP. 24 RGE. 15 ~~080~~ or (W)

COUNTY Stafford

Date Well Completed 8-3-64

Plugging Commenced 2-28-86

Plugging Completed 2-28-86

LEASE OPERATOR Chase Well Service, Inc.

ADDRESS P. O. Box 355, Great Bend, Kansas 67530

PHONE#(316) 793-9556 OPERATORS LICENSE NO. 6123

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Arbuckle Depth to Top 4410 Bottom T.D. 4514

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Water	Surface	203	8-5/8		None
				5-1/2	4405	None
				4-1/2	4344-4505	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
5 1/2" rubber plug @ 800', 30 sks. cement spotted at 800' through tubing, let set 1 hr.,
50 sks. down tubing at 500' into 5 1/2". Circ. to surface, wait 2 1/2 hrs., 70 sks. down
casing, circ. out braden head, wait, pump 25 sks. into braden head.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Kenneth J. Link

(Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kenneth J. Link

(Address) Kenneth J. Link, President
P. O. Box 355, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 86



Loneita Barry
Loneita Barry, Notary Public
STATE CORPORATION COMMISSION

REC'd MAR 11 1986
3-11-86
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84