

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Stafford County, Sec. 36 Twp. 24 Rge. 15 (E) W (W)
 Lease Owner Tomlinson-Kathol, Inc.
 Lease Name Saterlee Well No. A-3
 Office Address Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed _____ 19____
 Application for plugging approved _____ 19____
 Plugging commenced 7-27-61 _____ 19____
 Plugging completed 8-1-61 _____ 19____
 Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot.
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4240 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	283'	None
				4-1/2"	4239'	2519'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4213', ~~ran~~ ran sand to 4150' and dumped 5 sacks of cement @ 4150' with dump bailer. Pulled 4 1/2" casing. Mudded hole to 250', set 10' rock bridge to 240' and ran 20 sacks of cement @ 240'. Mudded to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Knight Casing Pulling Co. STATE CORPORATION COMMISSION
 Address Chase, Kansas

RECEIVED

STATE OF Kansas COUNTY OF Rice
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Noel J. Knight
Chase, Kansas
 (Address)

AUG 11 1961
8-11-61

CONSERVATION DIVISION
WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 7th day of August, 1961

My commission expires May 20, 1964
Milton J. Volin Notary Public.



C O P Y

December 18, 1957

Rupp-Ferguson Oil Co.
522 Union Center
Wichita, Kansas

Rupp-Ferguson A-3 Satterlee
NE NW NE, Sec. 36-24-15W,
Stafford, County, Kansas

Gentlemen:

Samples and drilling time on the captioned well were examined from 3500 feet to the total depth of 4240 feet. All formation tops and depths are with reference to Kelly bushing measurements. Following are the formation tops as determined from sample analysis:

<u>Formation</u>	<u>Elevation</u>	<u>Samples</u>
Heebner	2001 Ground	3598 (-1592)
Toronto	2003 Derrick Floor	3620 (-1614)
Douglas	2006 Kelly Bushing	3638 (-1632)
Brown Lime		3747 (-1741)
Lansing-Kansas City		3767 (-1761)
Reworked Mississippian		4163 (-2157)
Kinderhook		4215 (-2209)
Total Depth		4240 (-2234)

One drill stem test was run in the Mississippian. Following are zones of porosity as determined from sample analysis.

LANSING-KANSAS CITY

3802-3807 White to buff semi-chalky limestone, trace fine vugular porosity and a very slight trace of stain.

3831-3840 Buff sucrosic granular and chalky limestone, fine vugular porosity, no staining.

3933-3937 Buff semi-chalky and pieces oolitic limestone show some porosity, no staining.

3943-3949 Same as above.

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1961

CONSERVATION DIVISION
Wichita, Kansas