

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County. Sec. 27 Twp. 24 Rge. (E) 13 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4 SW/4 NW/4

Lease Owner J. D. Ferrell Drilling Co., INC.

Lease Name Campbell #1 Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 6-28 19 49

Application for plugging filed 7-24 19 49

Application for plugging approved 7-24 19 49

Plugging commenced July 24, 1949 19

Plugging completed August 2, 1949 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. Stough

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 $\frac{1}{2}$		3038

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole to 4200'. Run 5 sacks of cement.
Mudded hole to 250'. Set rock bridge and run 15 sacks of cement.
Mudded hole to 30'. Set rock bridge and run 10 sacks of cement.
Well Completed

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. D. Ferrell Drlg Co
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. D. Ferrell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. Ferrell

Box 163, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of August, 1949

Notary Public

My commission expires Oct 15, 1951

PLUGGING
FILE SEC 27 T24 R15W
BOOK PAGE 108 LINE 26

WELL LOG

J. D. FERRELL DRILLING CO., INC.
& CROWN OIL CO., INC.
CAMPBELL B-1

Sec. 27; T-24S-R-15W
SW/4 SW/4 NW/4
County Stafford

Total Depth: 4246'
Comm: 4-18-49 Comp: 5-5-49
Contractor: J.D.Ferrell Drilling Co., Inc.
Issued: 7-5-49 Rotary O-4246'

Elevation: 2033 DF
Production: Dry

Figures Indicate Bottom of Formations:

cellar	6
clay	32
sand	110
shale & shells	305
sand	335
shale	375
shale & shells	385
red bed & shells	495
shale & shells	580
red bed & shale	960
shale	1020
Anhydrite	1275
shale & shells	1575
sand & shale	1775
shale & lime	1975
lime	2130
lime & shale	2520
lime	2650
lime & shale	3809
lime	3870
lime & shale	3905
lime	4073
lime & shale	4163
conglomerate	4203
lime, Cherty	4206
Mississippi	4230
sand & shale	4240
chert	4246
Total Depth	4246

Tops:

Heebner	3644
Top K.C.	3801
Base K.C.	4177
Mississippi	4206
Kinderhook shale	4225
Kinderhook sand	4230
Total Depth	4246

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily Drilling Reports.

J.D.FERRELL DRILLING CO., INC.,

BY: *J.W. Railseack*
J.W. RAILSEACK - Sec. Treas.

Subscribed and sworn to before me this 5th day of July, 1949.

My Commission Expires:

Merle V. ...
Notary Public

Oct. 15, 1951

PLUGGING
FILE SEC 27 24 R15W
BOOK PAGE 108 LINE 26

RECEIVED
CORPORATION-DIV.
AUG 1 3 1949
STATE CORPORATION
COMMISSION