


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 27 Twp. 24 Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Musgrove Drilling Company
Lease Name DYKES Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 7-22-61 19
Application for plugging filed verbally 7-21-61 19
Application for plugging approved verbally 7-21-61 19
Plugging commenced 7-22-61 19
Plugging completed 7-23-61 19
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud to 240'
Set 1st plug at 240' w/20 sx cement & 1/4 sx hulls
Filled hole w/heavy mud to 40'
Set 2nd plug at 40' w/15 sx cement & 1/4 sx hulls

RECEIVED
STATE CORPORATION COMMISSION
8-1-61
AUG 1 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Drilling Company
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Emil E. Bowers (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 61

Don Jaye Dyke
Notary Public.

My commission expires June 16, 1963

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Drilling Company
 CONTRACTOR: Musgrove Drilling Company
 FARM: DYKES #1
 LOCATION: C NE SE Sec. 27-24-15
 Stafford County, Kansas
 COMMENCED: July 9, 1961
 COMPLETED: July 22, 1961

0	253	Surface soil
253	278	Shale
278	1005	Clay & Red Bed
1005	3775	Lime & shale
3775	4216	Lime
4216	4282	Lime & shale
4282	4345	Lime
4345	4364	Cherty lime
4364	4386	Chert, Lime & shale
4386	4475	Lime & shale
4475	4515	Sand & shale
4515	4560	Lime
4560		Total Depth

ELEVATIONS: 2019' G. L.
 2022' D. F.
 2024' K. B.

ELECTRIC LOG TOPS:

Heebner	3620'	(-1596)
Brown Lime	3768'	(-1744)
Lansing	3781'	(-1757)
Base Kansas City	4064'	(-2040)
Mississippian	4183'	(-2159)
Kinderhook	4205'	(-2181)
Viola	4282'	(-2258)
Simpson	4404'	(-2380)
Simpson Sand	4416'	(-2392)
Arbuckle	4493'	(2469)
TOTAL DEPTH	4560'	(-2536)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 1 1961
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8-5/8" surface casing at 253' w/185 sx cement

DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the DYKES #1, C NE SE, Section 27-24S-15W, Stafford County, Kansas, as reflected by the files of Musgrove Drilling Company.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 31st day of July, 1961.

Leah Faye Hefke
 Leah Faye Hefke, Notary Public

My commission expires June 16, 1963.