

STATE OF KANSAS


STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 36 Twp. 24 Rge. (E) 15(W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Wilkinson Drlg. Co.

Lease Name Prager Well No. 3

Office Address Union Center Bldg., Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed March 10, 1966

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production July 1965

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Letter

Name of Conservation Agent who supervised plugging of this well A. Elving

Producing formation Depth to top Bottom Total Depth of Well 4390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand to 4100 - dump 5 sax cement - pull 2631.55 ft. 5 1/2" pipe - mud to 260 ft.
10 ft. rock bridge - dump 25 sax cement - mud to 40 ft. - 10 ft. rock bridge.
Dump 10 sax cement to surface.

RECEIVED
3-29-66
MAR 29 1966

Conservation Division
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas COUNTY OF Stafford, ss.

Ralph Comstock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Ralph Comstock

(Address)

Stafford, Ks

SUBSCRIBED AND SWORN to before me this 17 day of March, 1966

My commission expires

June 4-1968

Notary Public.



WILKINSON DRILLING, INC.
1121 Union National Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1966

December 21, 1959

Company - WILKINSON DRILLING, INC.
Contractor - Company Tools
Commenced - December 5, 1959
Completed - December 17, 1959
Total Depth - 4390'

Location - NE NE SE, Sec. 36-24^S-15^W,
Stafford County, Kansas
Elevation - 2006' KB
Casing - 8 5/8" @ 279' w/290 sacks
5 1/2" @ 4382 w/75 sacks

FIGURES INDICATE BOTTOMS OF FORMATIONS

<u>Depth</u>	<u>Formations</u>
0 - 160	Sand.
160 - 1840	Shale and shells.
1840 - 1920	Lime and shale.
1920 - 2170	Lime.
2170 - 3155	Lime and shale.
3155 - 3188	Lime.
3188 - 3500	Lime and shale.
3500 - 3597	Lime.
3597 - 3640	Shale and lime.
3640 - 3743	Shale and silty shale.
3743 - 4140	Lime and shale streaks.
4140 - 4165	Shale.
4165 - 4193	Chert.
4193 - 4248	Shale.
4248 - 4342	Chert and lime.
4342 - 4379	Shale.
4379 - 4390	Dolomite.

We hereby certify the above and foregoing to be a true and correct copy of the Log on the PRADGER #3, located in the NE NE SE, Sec. 36-24^S-15^W, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson
Walter M. Wilkinson

Subscribed and sworn to before me this twenty-first day of December, nineteen hundred and fifty-nine.

Carolyn K. Moore
Carolyn K. Moore

My commission expires January 2, 1961.