


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 36 Twp. 24 Rge. 15 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner Wilkinson Drilling Company
Lease Name Proeger Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-16-65 _____ 19____
Plugging completed 6-22-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278'	None
				5-1/2"	4388'	2117'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4391', set plug @ 4130', sanded hole to 4080' and dumped 5 sacks of cement @ 4080' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 260' and dumped 2 sacks of cement @ 260' with dump bailer. Bailed hole and dumped 23 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
6-29-65
JUN 29 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of June, 1965

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

1121 Union National Building

Wichita 2, Kansas

September 23, 1959

PRAEGER #2

Company - WILKINSON DRILLING, INC.
 Contractor - Company Tools
 Commenced - September 8, 1959
 Completed - September 22, 1959
 Total Depth - 4391'

Location - NW SW SE, Sec. 36-24s-15w,
 Stafford County, Kansas
 Elevation - 2010' KB
 Casing - 8 5/8" @ 287' w/290 sacks
 5 1/2" @ 4388' w/100 sacks
 TD 4391'

FIGURES INDICATE BOTTOMS OF FORMATIONS

<u>Depth</u>	<u>Formations</u>
0 - 120	Sand.
120 - 282	Sand, clay, and shale.
282 - 952	Shale and shells.
952 - 970	ANHYDRITE.
970 - 1625	Shale and shells.
1625 - 1915	Shale and lime.
1915 - 3764	Lime and shale.
3764 - 4164	Lime.
4164 - 4190	Mississippi.
4190 - 4299	Chert and shale.
4299 - 4391	Chert and lime.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 7 1960
 CONSERVATION DIVISION
 Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the Log on the PRAEGER #2, located in the NW SW SE, Sec. 36-24s-15w, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson
 Walter M. Wilkinson

Subscribed and sworn to before me this twenty-third day of September, nineteen hundred and fifty-nine.

Carolyn K. Moore
 Carolyn K. Moore

My commission expires January 2, 1961.