


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 36 Twp. 24 Rge. 15 (E) W (W)



Location as "NE/CNW&SW" or footage from lines NE NE NE
Lease Owner Tomlinson-Kathol, Inc.
Lease Name Saterlee Well No. A-1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7-24-61 _____ 19____
Plugging completed 7-27-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	344'	None
				5-1/2"	4459'	2251'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4440', sanded to 4150' and dumped 5 sacks of cement @ 4150' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 250', set 10' rock bridge to 240' and ran 20 sacks of cement @ 240'. Mudded to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
8-11-61
AUG 11 1961

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1961

My commission expires May 20, 1964

Milton J. Volter
Notary Public.



MAYFIELD & SMITH
Consulting Petroleum Geologists
909 Central Building
Wichita, Kansas

February 20, 1957

Petroleum Management, Inc.
Central Building
Wichita, Kansas

Re: Petroleum Management, Inc.
#1 Satterlee
NE NE Sec. 36-24S-15W
Stafford County, Kansas

Dear Sirs:

Following is a geological report on the above captioned well. This well is originally drilled by McKnab Drilline Company. The original rotary depth was 4404'. All cuttings and samples were examined from 4404' to 4460', the new rotary total depth.

GEOLOGICAL TOPS

	Elevation 2015 KB	
Heebner	3600	-1585
Brown Lime	3745	-1730
Lansing	3764	-1749
Conglomerate	4147	-2132
Mississippi	4156	-2141
Kinderhook	4189	-2174
Viola	4247	-2222
Simpson	4324	-2309
Arbuckle	4383	-2368
Total Depth	4460	-2445

ARBUCKLE

- 4404-10 Samples poor, no analysis could be made.
- 4410-17 Dolomite, tan to gray buff, mostly fine crystalline, trace of medium crystalline, dense dolomite.
- 4417-25 Dolomite, fine crystalline with slight show of oil, slight odor, fair porosity.
- 4425-4460 Dolomite, white fine to medium crystalline, fair porosity, no show.

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1961
CONSERVATION DIVISION