


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
1101 North Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 35 Twp. 24 Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines. C. N/2 N/2 NE/4  
Lease Owner Wilkinson Drlg. Inc. & Chief Drlg. Co., Inc.  
Lease Name GILES Well No. 1  
Office Address Box 797 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7/14 19 62  
Application for plugging filed 7/14 19 62  
Application for plugging approved 7/14 19 62  
Plugging commenced 7/14 19 62  
Plugging completed 7/14 19 62  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus - Nickerson, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4443 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Gravel		0	258		258	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used; state the character of same and depth placed, from feet to feet for each plug set.

Set wooden plug at 250' with 20 sacks cement thru drill pipe  
1/3 sacks hulls, set wooden plug at 40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7-17-62  
JUL 17 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Box 797 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
V. Richard Hoover, Pres. Chief Drlg. Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard Hoover  
Box 797 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 1962.

Carmen Reinhardt Leiker  
Carmen Reinhardt Leiker, Notary Public.

My commission expires Jan. 26, 1963

INVOICED

DATE 7/17/62

INV. NO. 5388-W

WELL LOG

Wilkinson Drilling, Inc. &  
Chief Drilling Co., Inc.  
Box 797  
Great Bend, Kansas

GILES #1  
C N/2 N/2 NE/4 Sec. 35-24S-15W  
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 6-30-62  
Completed: 7-14-62  
D & A

**RECEIVED**  
STATE CORPORATION COMMISSION

Casing Record: 8-5/8" @ 258' w/245 sacks Sunset cement

JUL 17 1962

CONSERVATION DIVISION  
Wichita, Kansas

FORMATION	FROM	TO	ELEVATION
Shale & Sand	0	258	2013 Gr.
Red Bed & Sand	258	976	2015 D.F.
Anhydrite	976	998	2018 K.B.
Shale & Shells	998	1760	
Shale	1760	1890	
Lime & Shale	1890	1970	
Lime	1970	2500	
Lime & Shale	2500	2790	
Lime	2790	2905	
Lime & Shale	2905	3225	
Lime	3225	3445	
Lime & Shale	3445	3570	
Lime	3570	4145	
Lime & Chert	4145	4295	
Chert	4295	4338	
Chert & Lime	4338	4358	
Lime, Shale & Chert, Sand	4358	4394	
Lime	4394	4423	
Shale & Sand	4423	4336	
Arbuckle Dolemite	4436	4443	
Total Depth	4443		

FORMATION TOPS	
Anhydrite	976 +1042
Heebner	3597 -1579
Toronto	3619 -1601
Douglas	3641 -1623
Brown Lime	3744 -1726
Lansing	3755 -1737
Base Kansas City	4040 -2022
Conglomerate	4130 -2112
Kinderhook	4169 -2151
Kinderhook Viola	4196 -2178
True Viola	4223 -2205
Simpson	4346 -2328
Arbuckle	4436 -2418
Total Depth	4443 -2425

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C N/2 N/2 NE/4 Sect. 35-24S-15W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 16th day of July, 1962.

*Carmen Reinhardt Leiker*  
Carmen Reinhardt Leiker, Notary Public

My commission expires: Jan. 26, 1963.