

96
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1964
10-29-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Giles Well No. # 1

Location SE SE NE Sec. 35 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4300

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:30PM Day 28th Month Oct. Year 1964

The Above well was plugged as follows:

224' of 8 5/8" surface pipe, cement circulated. 4300' of 4 1/2" long string,
cemented with 125 sacks. Top perforation 4168'. Bottom of the hole was
sanded to 4160', and cemented with 3 sacks. Fluid in the hole was at a 60'
level. Bridge plug was pushed to 220', and 10' of rock bridge added. 10
sacks of cement was mixed in barrel and put on plug through the dump bail-
er, and let set over-night. Next morning hole was bailed dry, and 15 sacks
of cement added to the plug. Hole was filled with mud to 40', and 10' of
rock bridge, and cemented with 10 sacks to the base of the cellar. 2142'
of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/29/64

INV. NO. 42-11