

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-131-20203-00-00
Spot: SENE Sec/Twnshp/Rge: 13-4S-13E
990 feet from N Section Line, 560 feet from E Section Line
Lease Name: KING Well #: 1
County: NEMAHA Total Vertical Depth: 3850 feet

Operator License No.: 34232
Op Name: MUSTANG FUEL CORPORATION
Address: 9800 N. OKLAHOMA AVE.
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3605		100 SX
SURF	8.625	334		220 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2015 11:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: HURRICANE SERVICES, IN Company: BRAD BUTLER Phone: (316) 303-9515

Proposed Plugging Method: Open well and blow down. If pressure exists, use a pump truck to kill well. MIRU WORND WH. NU 7-1/16 5K hydraulic BOP (w/ blind rams on bottom and 2-3/8 2 standard pipe rams on top) RIH w/ WL and set 5-1/2 2 CIBP at +/- 3489 2. Dump 2 sks of cement on top of plug POOH w/ WL and RIH w/ 3-1/8 2 perf guns loaded w/ 4 Big Hole charges at 90 degree phasing to shoot the following intervals: +/- 1288 2 (Top of Kansas City) 90 2 (50 2 below surface casing) RIH w/ 2-3/8 2 tbg to 2500 2 and pump a gel spacer to +/- 1300 2. Spot 25 sks across perfs at 1288 2 POOH to 1200 2 and pump gel spacer from 1200-400 2. Cement 390 2-Surface using +/- 120 sks. 60/40 Poz w/ 4% gel additive POOH and LD tubing Cut off casing at surface and cap Report results to KCC after operations have ceased.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 04/22/2015 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

CIBP SET AT 3480' WITH 2 SACKS OF CEMENT ON TOP. PERFORATED THE CASING AT 1400' AND 390'. LOADED THE CASING UP WITH GEL. TUBING SET AT 1410' AND PUMPED 25 SACKS OF CEMENT. PULLED TUBING OUT AND HOOKED ON TO THE CASING AND CIRCULATED CEMENT TO THE SURFACE ON THE INSIDE AND OUTSIDE FROM 390' TO SURFACE.

Top	Bot	Thru	Comments
3539	3542		

RECEIVED
KCC DIST # 3
DEC 21 2015
CHANUTE, KS
TH

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

DEC 23 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
12-30-15