

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-20871-00-00  
Spot: NWNWENW Sec/Twnshp/Rge: 26-8S-17W  
290 feet from N Section Line, 1340 feet from W Section Line  
Lease Name: HRABE Well #: 3-26  
County: ROOKS Total Vertical Depth: 3448 feet

Operator License No.: 4472  
Op Name: N.F. PRODUCERS, INC.  
Address: 1236 N. FAVER DR  
CASTLE ROCK, CO 80109

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3217		
PROD 4		3447		125 SX
SURF	8.625	259		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2015 10:00 AM  
Plug Co. License No.: 34366 Plug Co. Name: NAE, INC.  
Proposal Rcvd. from: BRETT HILDEBRAND Company: NAE, INC. Phone: (785) 871-7311

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/1000# hulls.  
Casing leaks from 1735' - 2606'.  
CIBP at 3217'.  
Production perforations: 3172' - 3297'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/12/2015 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforate at 1325', 850' and 255'. Ran tubing to 3200' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2200' and pumped 125 sx cement w/400 # hulls. Pulled tubing to 1300' and pumped 175 sx cement w/400 # hulls to circulate annulus and 4 1/2" casing to surface. Pulled all tubing. Topped off 4 1/2' casing w/25 sx cement.

GPS: 39.33515 -099.19000

Perfs:

Top	Bot	Thru	Comments
3295	3297		
3232	3234		
3172	3174		

Remarks: SWIFT SERVICES TICKET # 28741

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

CM

DEC 10 2015

Received  
KANSAS CORPORATION COMMISSION

DEC 30 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

No  
12-30-15