

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20646-00-01
Spot: SENENWNW Sec/Twnshp/Rge: 33-9S-24W
4878 feet from S Section Line, 4072 feet from E Section Line
Lease Name: HOETING UNIT Well #: 4-3
County: GRAHAM Total Vertical Depth: 4119 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4111		150 SX
SURF	8.625	265		160 SX

Well Type: EOR UIC Docket No: E19789.3 Date/Time to Plug: 12/03/2015 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/900 # hulls.
Perforations at: 3906' - 3910', 4006' - 4009', 4031' - 4034', 4042' - 4050', 4064' - 4068'.
Squeezed at 1555' - 1580' w/15 sx cement, 2138' w/65 sx cement, 2694' - 2727' w/75 sx cement, 2969' - 3001' w/15 sx cement.
2710' - 2722' Anguard.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2015 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3850' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 3231' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2228' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1208' and pumped 120 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement. Tied on to backside and squeezed with 130 sx cement and 160 # hulls.

GPS: 39.23232 -100.01038

Perfs:


Top	Bot	Thru	Comments
4064	4068		
4042	4050		
4031	4034		
4006	4009		
3906	3910		

Remarks: HURRICANE SERVICES TICKET # 100608

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

cm

DEC 09 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 21 2015

CONSERVATION DIVISION
WICHITA, KS

no
12.30.15
cc to UIC