

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25751-00-00
Spot: NWNWSWNE Sec/Twnshp/Rge: 29-17S-14W
1400 feet from N Section Line, 2580 feet from E Section Line
Lease Name: DIRREEN-WAGNER UNIT Well #: 1
County: BARTON Total Vertical Depth: 3451 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3448	2428	160 SX
SURF	8.625	850		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2015 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 2428'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface w/70 sx cement. Pulled casing and hole stayed full.

GPS: 38.54629 -098.89465

Perfs:

Top	Bot	Thru	Comments
3373	3379		
3310	3314		
3290	3294		
3256	3260		
3128	3134		
3118	3122		

Remarks: GLOBAL TICKET # 2570

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 14 2015

DEC 21 2015

CONSERVATION DIVISION
WICHITA, KS

no 12-30-15