

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25626-00-00
Spot: NESWSE Sec/Twnshp/Rge: 17-17S-14W
1185 feet from S Section Line, 1685 feet from E Section Line
Lease Name: MORGENSTERN Well #: C-1
County: BARTON Total Vertical Depth: 3404 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3435	2100	150 SX
SURF	8.625	908		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2015 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS Phone: (785) 445-2353

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Cut casing at 2100' leaving 1335' of 5 1/2" casing in well.
50 joints pulled avg. 42'.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded bottom back and spotted cement on top at 2150'. Cut casing at 2100'. Pulled casing to 1350' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300' and pumped 85 sx cement. Circulated cement to surface. POOH. Cellar stayed full.

GPS: 38.56792 -098.89163

Perfs:

Top	Bot	Thru	Comments
3365	3368		
3348	3354		
3184	3194		
3174	3178		

Remarks: GLOBAL TICKET # 2572

Plugged through: CSG

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

DEC 30 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

DEC 21 2015

Handwritten: No 12-30-15