

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-21478-00-00  
Spot: SWSWNENE Sec/Twnshp/Rge: 13-31S-33W  
4034 feet from S Section Line, 1261 feet from E Section Line  
Lease Name: THOMPSON Well #: 2  
County: SEWARD Total Vertical Depth: 2800 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2800	0	WITH 575 SX CMT
SURF	8.625	584		WITH 375 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2015 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/18/2015 12:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

TIH W/OVERSGOT AND TAG TBG AT 1290'. IT FELL TO 1449'. UNABLE TO LATCH ON TO FISH. 1ST PLUG AT 1449' WITH 50 SX CMT. TAGGED TOC @ 877'. 2ND PLUG AT 877' TO 0' WITH 100 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2644	2703		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
DEC 21 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
DEC 23 2015  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

no  
12-30-15