

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22108-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 4-19S-29W
4687 feet from S Section Line, 1087 feet from E Section Line
Lease Name: PHYLLIS "A" Well #: 1-4
County: LANE Total Vertical Depth: 4667 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2125		CEMENTED WITH 200 SX CMT. 20 SX CMT TO PIT
PROD	5.5	4666	0	WITH 225 SX CMT
SURF	8.625	285		WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2015 9:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: JOHN DAVIDSON Company: WILD WEST WELL SERVICE, INC. Phone: (785) 798-4644

Proposed Plugging Method: PUMP 30 SX CMT & 250-300# HULLS FOR BOTTOM. CIRCULATE CMT FROM 2210' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2015 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT & 150# HULLS. DISPLACE TO 4456'. PRESSURE TO 1000 PSI. RUN TBG TO 2142' & CIRCULATE CMT TO SURFACE WITH 200 SX CMT. TOOH WITH TBG & TOP OFF 5 1/2" CASING WITH 10 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS. PRESSURE TO 400#.

Perfs:

Top	Bot	Thru	Comments
4452	4456		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SA

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

RECEIVED
DEC - 7 2015
KCC DODGE CITY

DEC 21 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MP
12-30-15