

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-00472-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 18-30S-32W
2427 feet from S Section Line, 2394 feet from E Section Line
Lease Name: LEONARD FW Well #: 1
County: HASKELL Total Vertical Depth: 2745 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING,
Address: 1200 MAIN ST PO BOX 818
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1450		WITH 5 SX CMT
PROD	7	2745	0	WITH 750 SX CMT
SURF	10.75	559		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/07/2015 12:30 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 1450-1460'. WITH 4 SX CMT. PRESSURE CASING TO 300-500#. TBG TO 600' CMT TO SURFACE. TIE ONTO BACKSIDE & CHECK,

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2015 3:50 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 1450' WITH 5 SX CMT. CASING HELD AT 300 PSI. TBG TO 600' WITH 110 SX CMT TO SURFACE. TIE ONTO BAKSIDE & PUMPED 7 SX CMT. PRESSURE TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2728	2740		
2682	2704		
2652	2662		

Remarks: USED CLASS C CEMEBNT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

DEC 21 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
DEC 11 2015
KCC DODGE CITY



5A

Form CP-2/3

mp
12.30.15