

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21183-00-01
Spot: SESWSENE Sec/Twnshp/Rge: 27-12S-32W
2420 feet from N Section Line, 753 feet from E Section Line
Lease Name: JANOVA Well #: 2-27
County: LOGAN Total Vertical Depth: 4715 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4707		170 sx
SURF	8.625	220		165 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2015 1:45 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING CO. Phone: (316) 265-3000

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls and 14 sx gel.
Perforations at 4119' - 4123', 4597' - 4604' and 4589' - 4593'.
Port Collar at 2550' w/255 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2015 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 100 sx cement w/425 # hulls, followed by 14 sx gel, followed by 260 sx cement. Topped off casing with 40 sx cement. Tied on to backside and squeezed with 20 sx cement. Shut in pressure 300 psi.

GPS: 38.98254 -100.85387

Perfs:

Remarks: SWIFT CEMENT TICKET # 28874

Plugged through: CSG

District: 04

Signed _____


(TECHNICIAN)

CM

DEC 09 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 21 2015

CONSERVATION DIVISION
WICHITA, KS

Dec 30-15