

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-21087-00-00
Spot: NENESE Sec/Twnshp/Rge: 10-12S-16W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: DICKINSON A Well #: 8
County: ELLIS Total Vertical Depth: 3353 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3350		175 SX
SURF	8.625	117		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2015 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: IVAN R. EDSALL Company: DREILING OIL, INC. Phone: (785) 625-8327

Proposed: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Plugging: 2 3/8" tubing was stuck in the hole w/no stretch, leaving 3300' of tubing in the well.
Method: Squeezed on 02/18/1985 w/200 sx cement and on 02/20/1985 at 608'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2015 12:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked to tubing and pumped 40 bbl of water to test ability to pump into tubing. Good rate and good vacuum at the end. Hooked pump truck up and pumped 125 sx cement. Pressure climbed to 700 psi and started to blow out the backside. Finished mixing cement and displace the tubing to 1750' w/7 bbl of water. The pressure climbed to 700 psi once again. Rigged up perforator and shot through the tubing at 1700' and 1005'. Hooked to tubing and pumped 140 sx cement at 350 psi with good returns of cement. Dug out cellar and found an old style of braden head with no way to hook on to. Cement was around the head and in the cellar. Will check after cutting off the head for fill up.
12/07/2015- Braden head cut off and topped with 1 1/2 yards of ready mix by Ellis County Concrete.

GPS: 39.02330 -099.0765

Perfs:

Top	Bot	Thru	Comments
3072	3227		
2781	2787		

Remarks: ALLIED CEMENTING TICKET # 55403

Plugged through: TBG

District: 04

Signed _____

Ray Dinkel

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 21 2015

CONSERVATION DIVISION
WICHITA, KS

no 12-30-15

REC 11 9 2015