

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20955-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 31-8S-17W
1727 feet from N Section Line, 2202 feet from W Section Line
Lease Name: RUSS Well #: 6
County: ROOKS Total Vertical Depth: 3426 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3408		150 SX
SURF	8.625	167		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2015 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DENNIS MICK Company: CITATION OIL AND GAS CORP. Phone: (785) 639-6314

Proposed Plugging Method: Ordered 470 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Production perforations: 3323' - 3325' and 3404' - 3414'.
Knocked out CIBP at 3095'.
DV Tool at 1307' with unknown amount of cement.
Squeezed at 2298' - 2319' w/200 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2015 9:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3332' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 3125' and pumped 175 sx cement w/250 # hulls. Pulled tubing to 1300' and pumped 130 sx cement w/150 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/65 sx cement. Hooked to 8 5/8" x 5 1/2' annulus and pumped 50 sx cement. No pressure. Cement came around casing hanger.

GPS: 39.31641N -099.26195W

Perfs:

Top	Bot	Thru	Comments
3404	3414		
3323	3325		

Remarks: ALLIED TICKET # 55086

Plugged through: TBG

District: 04

Signed Pat Bedore

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

DEC 09 2015

DEC 30 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

no 12-30-15