

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-131-20240-00-00  
Spot: NESENWNW Sec/Twnshp/Rge: 1-1S-14E  
819 feet from N Section Line, 1064 feet from W Section Line  
Lease Name: SNYDER Well #: 2-15  
County: NEMAHA Total Vertical Depth: 3611 feet

Operator License No.: 31772  
Op Name: BLACK STAR 231 CORP.  
Address: LIVESTOCK EXCHANGE BLDG 1600  
KANSAS CITY, MO 64102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	252		135 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/15/2015 1:00 PM  
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC  
Proposal Revd. from: JIM PRYOR Company: ELITE CEMENTING AND ACID SE Phone: (816) 560-7300

Proposed Plugging Method: 50' @ TD, 50' @ Top Hinton, 50' @ Top Mississippian, 50' @ Top Checokee, 50' @ Top Kansas City, 50' base of surface casin and 60' to land surface.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 08/15/2015 2:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

HAD DRILL PIPE RAN DOWN TO 3611' AND PUMPED 15 SACKS OF CEMENT.  
PULLED THE DRILL PIPE UP TO 2511' AND PUMPED 15 SACKS OF CEMENT.  
PULLED THE DRILL PIPE UP TO 2264' AND PUMPED 15 SACKS OF CEMENT.  
PULLED THE DRILL PIPE UP TO 1380' AND PUMPED 15 SACKS OF CEMENT.  
PULLED THE DRILL PIPE UP TO 300' AND PUMPED 35 SACKS OF CEMENT.  
PULLED THE DRILL PIPE UP TO 60' AND CIRCULATED 20 SACKS OF CEMENT TO THE SURFACE.

Perfs:

RECEIVED  
KCC DIST #3  
DEC 21 2015  
CHANUTE, KS

TH

Remarks:

Plugged through: DP

District: 03

Signed Taylor Herman  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 23 2015  
CONSERVATION DIVISION  
WICHITA, KS

no  
12-30-15