

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20596-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 27-4S-22W
670 feet from N Section Line, 600 feet from W Section Line
Lease Name: SANSOM Well #: 6
County: NORTON Total Vertical Depth: 3720 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3690		
PROD	4.5	3502		150 SX
SURF	8.625	218		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2015 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DANIEL WINDHOLZ Company: BLACK DIAMOND OIL Phone: (785) 259-8403

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Bridge plug at 3690'.
Production perforations: 3646' - 3648', 3690', 3470' - 3471'.
3" liner 3376' - 3715'
PC at 1860' w/575 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2015 12:10 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3370' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2240' and pumped 100 sx cement w/200 #hulls. Pulled tubing to 850' and pumped 50 sx cement to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/15 sx cement. Visually checked 8 5/8" x 4 1/2" annulus and cement was to surface.
GPS: 39.68093N -099.79407W

Perfs:

Top	Bot	Thru	Comments
3646	3648		
3634	3635		
3584	3690		
3470	3471		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1948

Plugged through: TBG

District: 04

Signed _____ Received Pat Bedore
KANSAS CORPORATION COMMISSION (TECHNICIAN) CM

DEC 30 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

DEC 21 2015

Handwritten: 700
12-30-15