

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21145-00-00
Spot: SENESE Sec/Twnshp/Rge: 36-8S-18W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: THOMAS Well #: 2
County: ROOKS Total Vertical Depth: 3550 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3549		0 SX
SURF	8.625	216		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2015 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DENNIS MICK Company: CITATION OIL AND GAS CORP. Phone: (785) 639-6314

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 1320' with an unknown amount of cement.
Production perforations: 3000' - 3001'
Knocked out CIBP at 2885'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2015 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3272' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2800' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1300' and pumped 130 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/45 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 30 sx cement with no pressure. Cement came around casing hanger.

GPS: 39.31113N -099.27087W

Perfs:

Top	Bot	Thru	Comments
3000	3001		

Remarks: ALLIED TICKET # 55087

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

DEC 30 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

DEC 10 2015

No 12-30-15