

KANSAS

*el*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
7-31-72  
JUL 31 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Specter Pipe & Supply Inc.

Complete Address Box 169 Russell, Ks

Lease Name Satterlee-Twin Well No. 5

Location SE/NW/NW Sec. 36 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4402

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Lynch Casing Pulling Co.

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 11:00 AM Day 25 Month 7 Year 1972

The above well was plugged as follows:

278 ft 8 5/8 surface pipe cemented with 280 sacks. 4397 ft 5 1/2 long  
string cemented with 75 sacks. Open hole. Sand to 4200 ft, 5 sacks  
cement with bailer. Pulled 2300 ft 5 1/2. Pump 2 sacks hulls, 15 sacks  
gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. Russell Bilyester*  
Well Plugging Supervisor

INVOICED

DATE 8/1/72  
INV. NO. 6092-4