


KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 10-17-66
 OCT 17 1966
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Welch & Olson
 Complete Address: 353 Armour, Wichita, Kansas
 Lease Name Satterlee Well No. # 4
 Location NE NW NW Sec. 36 Twp. 24 Rge. 15 (E) (W) W
 County Stafford Total Depth 4402'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Knight Casing Pulling Company
 Address: Box 405, Chase, Kansas License No. 436
 Operation Completed: Hour 10:30AM Day 12th Month Oct. Year 1966

The Above well was plugged as follows:

277' of 8 5/8" surface pipe, cemented with 280 sacks. 4397' of 5 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole
was sanded to 4375', and cemented with 5 sacks, through the dump bailer.
2900' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed
in fluid to 270', rock bridge from 270' to 260'. 5 sacks of cement was mixed
in a barrel, and put on plug at 260', through the dump bailer, and let set
over-night. Next day hole was bailed dry, and 20 sacks of cement was added to
the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/17/66

INV. NO. 4105-W

Signed: Archie Elving
 Well Plugging Supervisor