


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION S<sub>W</sub>-S<sub>W</sub>-21<sub>W</sub>

SEC. 27 TWP. 24 RGE. 15<sup>W</sup>

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Cambell Campbell

Operator H. Ferrell Drilling Co. Address Great Bend - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 4325 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 5 7/8 - 426 ft. Circulated with cement -  
5 1/2" casing Set at 4231 ft. Plug back from bottom  
at 4230 ft with mud & chat - 15 sacks of cement  
dumped at 4230 ft. Shot off & Pulled the 5 1/2" casing  
Filled with mud to 250 ft - Set Rock Bridge &  
15 sacks of cement at 250 ft - Mud to 30 ft - Plug  
& 10 sacks of cement at the surface

RECEIVED

Conservation Div.  
8-8-49  
AUG 8 - 1949

C. H. Stough  
District Conservation Agent

Date 8-2-49

FL

PLUGGING  
FILE SEC 27 T 24 R 15<sup>W</sup>  
BOOK PAGE 108 LINE 26

STATE CORPORATION  
COMMISSION  
KANSAS