

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
SITE OF CONSERVATION
3-14-66
MAR 14 1966
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Mountain Iron & Supply
Complete Address: 200 Misco Bldg., Wichita, Kansas
Lease Name Praeger Well No. # 3
Location NE NE SE Sec. 36 Twp. 24 Rge. 15 (E) (W) W
County Stafford Total Depth 4390'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Comstock Pipe Pulling, Inc.
Address: Stafford, Kansas License No. 490
Operation Completed: Hour 11:30AM Day 10th Month March Year 1966

The Above well was plugged as follows:

279' of 8 5/8" surface pipe, cemented with 290 sacks. 4382' of 5 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole
was sanded to 4100', and cemented with 5 sacks, through the dump bailer.
2631' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was bailed down to 260', rock bridge from 260' to 250', and bridge plug,
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/14/66
INV. NO. 2853-u

Signed: Archie Elving
Well Plugging Supervisor