

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
6-23-65
JUN 23 1965CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Wilkinson Drilling, Inc.Complete Address: 805 UNION CENTER Bldg.
1121 Union National Bldg., Wichita, KansasLease Name Praeger Well No. # 2Location NW SW SE Sec. 36 Twp. 24 Rge. 15 (E) (W) WCounty Stafford Total Depth 4391'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 5:45 PM Day 22nd Month June Year 1965

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cemented with 200 sacks. 4388' of 5 1/2" long
string, cemented with 100 sacks. This is an open hole. Bottom of the
hole was sanded to 4380', and cemented with 5 sacks. Fluid level was up
in the hole. Bridge plug was pushed in fluid to 260', and 10' of rock
bridge on plug at 260'. 2 sacks of cement and 10% of Calcium Chloride
was mixed in barrel and put on plug at 250', through the dump bailer and
let set for 1 1/2 hours. Hole was bailed dry, and 23 sacks of cement was
added to the plug. Hole was filled with mud to 40', and 10' of rock bridge,
and cemented with 10 sacks to the base of the cellar. 2128' of 5 1/2" long string
was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 6/23/65INV. NO. 1356-W