

dl KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: STAFFORD

Location: NE-NE-NE Sec. 36 Twp. 24 Rge. 15 4E1 (W)

Name of Field: _____ Total Depth: 4460'

I have this date completed supervision of plugging of:

Lease Name: SATTERLEE Well No. 1

Operator's Full Name: TOMLINSON - KATHOL

Complete Address: 414 UNION CENTER WICHITA, KANS

Plugging Contractor: KNIGHT CASING PULLING

Address: CHASE, KANS License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

RECEIVED
STATE CORPORATION COMMISSION
8-4-61
AUG 4 1961
CONSERVATION DIVISION
Wichita, Kansas

Operation Completed: Hour 5³⁰ PM Day 27 Month JULY Year 1961

The above well was plugged as follows:

8 7/8 - 344' circ - 5 1/2 - 4459' TOP PERF - 4164'
SANDEN BOTTOM OF HOLE BACK TO 4150' W/5 3/4" CEMENT
THRU BAILER - PULLED 2200' 5 1/2 - FILLED HOLE W/MUD
TO 240' - ROCK BRIDGE W/20 3/4" CEMENT - FILLED W/MUD
TO 40' - ROCK BRIDGE W/10 3/4" CEMENT CAP TO BASE OF
CELLAR.

Signed: Orville Bussard
Conservation Division Agent

Reviewed: Harold H. Halls
Field Supervisor

Remarks:

INVOICED

DATE 8/14/61

INV. NO. 3566-W