

40  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

8-20-63  
AUG 20 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name V. E. Wiggins

Complete Address: P. O. Box 191, McPherson, Kansas

Lease Name Barstow "B" Well No. # 1

Location C W/2 N/2 SW Sec. 35 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4413

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Art Lamb Casing Pulling Co.

Address: Box 983, Hutchinson, Kansas License No. 440

Operation Completed: Hour 10.00AM Day 17th Month August Year 1963

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 225 sacks. 4407' of 5 1/2" long  
string, cemented with 125 sacks. Top perferation 3808'. Sanded to 3800',  
cemented with 5 sacks. Fluid level was up in the hole. Plug was pushed  
to 260', 10' rock bridge, cemented with 4 sacks cement, mixed and put  
on plug through bailer, let set over night. Next morning hole bailed  
down and 16 sacks cement was added to plug. Hole was filled with mud  
to 40', 10' rock bridge, cemented with 10 sacks to base cellar.  
3350' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/20/63

INV. NO. 9601-W