

15-047-21205-0000

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- A. MILLER "B" 2-14
Located: NW SW NW, Section 14-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 9, 1984

COMPLETED: September 15, 1984

TOTAL DEPTH: 4445'

LOG

CASING RECORD

0 - 90 Surface Soil and Sand
 90 - 260 Shale
 260 - 1114 Shale and Sand
 1114 - 1133 Anhydrite
 1133 - 1450 Shale
 1450 - 2170 Shale, Lime Stringers
 2170 - 4445 Lime and Shale

Ran 6 joints new 8 5/8", 23# casing.
 243.93' pipe set at 257' K.B.
 Cemented with 210 sacks 60/40 Pozmix,
 plug 3% cc. Plug down at 12:45 PM,
 9-9-84, by Howco.

Ran 108 joints 4 1/2", 10.5# casing.
 11 joints were used. 4428.87' pipe
 set at 4438' K.B. Cemented with
 100 sacks Lite and 125 sacks 50/50
 Pozmix, plus our regular additives.
 Plugged rathole and water well.
 Plug down at 1:00 PM, 9-15-85, by
 Howco.

Deviation Surveys: 1° at 2210'
3/4° at 4340'

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1985

CONSERVATION DIVISION
Wichita, Kansas