

*To be filed with State*

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-185-22954-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. Holl Company L.L.C. OPERATORS LICENSE NO. 5056  
P. O. Box 780167  
ADDRESS Wichita, Kansas 67278-0167 PHONE # (316) 684-8481

LEASE (FARM) Piland WELL NO. 1-26 WELL LOCATION W/2 SW NW COUNTY Stafford  
SEC. 26 TWP. 24S RGE. 15W (E) or (W) TOTAL DEPTH 4515' PLUG BACK TO \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A XX SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_  
SURFACE CASING SIZE 8 5/8" SET AT 323 KB CEMENTED WITH 250 SACKS  
CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill hole with heavy mud. 50 sacks  
at 1000'; 50 sacks at 320'; 10 sacks at 40' with 15 sacks in rathole. Use 60/40  
Pozmix with 6% gel.  
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? \_\_\_\_\_  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 4:00 PM, 3-24-94

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Vaughn Thompson PHONE # (316) 278-2131  
ADDRESS P. O. Box 129  
Sterling, Kansas 67579-0129

PLUGGING CONTRACTOR Sterling Drilling Company LICENSE NO. 5142  
P. O. Box 129  
ADDRESS Sterling, Kansas 67579-0129 PHONE # (316) 278-2131

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Richard L. Mead  
(Operator or Agent)  
Richard L. Mead, Vice President  
DATE: March 28, 1994

*Rec'd.  
3-28-94*

# STERLING DRILLING COMPANY

BOX 129  
STERLING, KANSAS 67579  
(316) 278-2131

SAMPLE LOG - - - - - PILAND #1-26  
Located: W/2 SW NW, Section 26-24S-15W  
Stafford County, Kansas

OWNER: F. G. HOLL L.L.C.  
ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: March 17, 1994  
COMPLETED: March 24, 1994.

TOTAL DEPTH: 4515' Driller  
4516' Logger

## LOG

0' - 190'	Surface Soil and Sand
190' - 326'	Shale
326' - 730'	Red Bed and Shales
730' - 1450'	Shale
1450' - 4515'	Lime and Shale

## CASING RECORD

Spudded at 1:30 PM, 3-17-94. Drilled 326' of 12 1/4" hole. Ran 8 joints 8 5/8", 23# casing. 311.02' pipe set at 323' K.B. Cemented with 250 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 6:00 PM, 3-17-94, by Howco. Ticket No. 641918. Good returns.

Plugged.

## DEVIATION SURVEYS

3/4 degree at 326'  
1 1/4 degree at 4214'  
2 degree at 4515'