

EP

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1963
 10-1-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Smith of Glen & Smith Casing Pulling has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Wilco Oil Inc.

Complete Address: Box 13528, Phoenix, Arizona

Lease Name: Klein Well No. # 1

Location: SW NE SE Sec. 2 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 3805 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

280' of 8 5/8" surface pipe, cemented to top. 3805' of
5 1/2" long string, cemented with 125 sacks. Top perforation
3650'. Push plug to 3600', and rock bridge, cement with
5 sacks. Fill hole with mud to 270', 10' rock bridge, cem-
ent with 25 sacks. Fill hole with mud to 40', 10' rock brid-
ge, cement with 10 sacks to base cellar.

Very truly yours,
Archie Elving
 Conservation Division Agent