

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 7 1963
 5-7-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers Inc. has this date requested permission to plug the following described well:

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name: Hawley "A" Well No. # 1

Location: C SE NW Sec. 7 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 4346 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Finch was instructed to plug the well as follows:

252' 05 8 5/8" surface Pipe, cemented with 200 sacks.
4344' of 5 1/2" long string cemented with 100 sacks. Plugged
back to 4278'. Perforated 4248' to 52'. Pushed plug to
4200', cemented with 5 sacks. Set 1st cementing plug at
225', 10' rock bridge, cement with 20 sacks. Fill hole with
mud to 40', 10' rock bridge, cement with 10 sacks to base
cellar.

Very truly yours,
Archie Elving
 Conservation Division Agent