

State of Kansas

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 20 1963  
 8-20-63

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Hopkins of Aylward Drilling Co. has this date requested permission to plug the following described well:

Mr. Hopkins guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kans.

Lease Name: Eichenberger "A" Well No. # 1

Location: NE NE NE Sec. 31 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4335 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Hopkins was instructed to plug the well as follows:

249' of 8 5/8" surface pipe, cemented with 200 sacks.  
Fill hole with mud to 260', 1st cementing plug, 1/4 sack  
hulls, cement with 20 sacks. Fill hole with mud to 40',  
2nd cementing plug, 1/4 sack hulls, cement with 10 sacks  
to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent