

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 31 1964

1-31-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Joe Cain, Jr. of Navajo Drilling Co. has this
date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Hudson Petroleum Co.

Complete Address: P. O. Box 333, Kansas City 3, ~~Missouri~~ KANSAS

Lease Name: Suiter Well No. # 1

Location: SE NW SE Sec. 24 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4215 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cain was instructed to plug the well as follows:

251' of 8 5/8" surface pipe, cement circulated. Fill hole
with drilling mud to 300', 1st cementing plug, bridge with
hulls, and cement with 40 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent