

State of Kansas



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 7-18-62
 JUL 19 1962
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 7 - 14 - 1962, 1961, authorized the following plugging operation:

Operator's full Name: Wilkinson Drig. Inc. & Chief Drig. Co., Inc.

Complete Address: Box 797, Great Bend, Kansas

Lease Name: Giles Well No. 1

Location: C N/2 N/2 NE/4 Sec. 35 Twp. 24S Rge. 15 (E)(W) X

County: Starrord Total Depth: 4443'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

258' of 8 5/8" surface pipe circulated with cement. Hole filled to 250' with heavy drilling mud. 1/2 sack hulls, 1st cementing plug and 20 sacks cement through drill pipe. Hole filled to 40' with heavy drilling mud. 1/2 sack hulls, 2nd cementing plug and 10 sacks cement to bottom of cellar. Rathole bridged and 2 sacks cement.

Very truly yours, .

Herman Justus

