

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1975
12-15-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rice of Sterling Drlg Co has this

date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Zenith Drlg Corp Inc

Complete Address: Suite 600 200 W Douglas Wichita, KS

Lease Name: Piland Well No. 1

Location: NW/NW Sec. 26 Twp. 24s Rge. 15 (E)(W) W

County: Stafford Total Depth 4420 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

266 ft 8 5/8 surface cemented with 225 sacks. Pump plug,


35 sacks cement to 250 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 2 sacks cement in

rat hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,


Conservation Division Agent