



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

7-10-82 RECEIVED
STATE CORPORATION COMMISSION
7-13-82
JUL 13 1982
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-185-21,629-0000

Dear Sir:

Mr. Jim SHRINER of Sterling Drilling Co has this date requested permission to plug the following described well:

Operator's Full Name: F. G. HOLL

Complete Address: 6927 E. Kellogg, WICHITA, KS 67207

Lease Name: CUMMINS Well No. 6-15

Location: C-SW-NE Sec. 15 Twp. 24 Rge. 15 (E) (W)

County: STAFFORD Total Depth: 4235'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Shriner was instructed to plug the well as follows:

1ST Plug @ 720' w/ 60 sky of Cement. 2ND plug @ 300' w/ 35 sky of cement. 3RD plug on solid bridge 40'-0' w/ 10 sky cement. Then circulate 10 sky in rat hole. Then plug water well w/ 3 sky cement. Cement pumped thru drill pipe with hole full of heavy mud. Plugging accomplished by Haliburton Co. Cement used was (over)

Very truly yours,

R. Barburton
Conservation Division Agent
Paul A. Suttie

11-11-54
11-11-54
11-11-54
11-11-54
11-11-54

50-50 posimit w/ 2% gel 3% CC. Amount of
Surface casing is 254' - 8 5/8 cement circulated,