

15-155-02142-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Reno County. Sec. 31 Twp. 22 Rge. 9 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW NW
Lease Owner Hinkle Oil Co
Lease Name Schewizer Well No. 2
Office Address 914 Union Nat'l Bank Bldg, Wichita, Kar
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 6/13/50 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/7/50 19
Plugging completed 6/13/50 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Durkee

Producing formation Depth to top Bottom Total Depth of Well 3723 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10	263	
				5 1/2	3718	3288' 3"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole to 3715. Run 6 sks cement.
Mudded hole to 265. Set 10' rock bridge.
Run 20 sks cement. Mudded to 10. Run
5 sks cement.
Well complete.

RECEIVED
Conservation Div. 6-20-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hinkle Oil Co
Address same as above

STATE OF Kansas, COUNTY OF Sedgewick, ss.

J. B. Hinkle (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Hinkle
(Address)

SUBSCRIBED AND SWORN to before me this 19 day of June, 1956

Mural A. Upton
Notary Public.

My commission expires Jan. 17, 1950

22-7377-s 4-49-10M

PLUGGING
FILE SECRET 22-7377-s
BOOK PAGE 11 LINE 38

COPY

15-155-02142-0000

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

HINKLE OIL CO-N. APPLEMAN CO.
Schweizer No. 2.

SEC. 31 T. 22 R. 9W
SE SW NW

Total Depth. 3723½'
Comm. 3-12-42 Comp. 3-31-42
Shot or Treated
Contractor. J. B. Hinkle
Issued. 6-13-42

County Reno

CASING:

10" 263'
5" 3718'

Elevation.

Production Pot. 1346 B.

Figures Indicate Bottom of Formations.

surface	263
red rock	330
anhydrite	355
shale	1250
lime brkn	1465
lime	1675
shale	1700
lime	1745
lime sdy	1800
lime brkn	2165
shale	2205
shale & shells	2360
shale	2425
lime & shale	2625
lime	2660
shale	2712
lime	2985
lime brkn	3005
lime	3040
shale	3054
lime brkn & shale	3142
shale & shells	3205
lime	3252
shale	3282
lime brkn	3330
lime	3528
shale	3540
lime	3590
shale	3670
lime sdy	3675
shale	3699
lime	3719
dolomite	3723½
Total Depth.	

Tops: K.G. lime 3203
Kinderhook 3507
Misener 3674
Viola 3699
Dolomite 3718

RECORDED
INDEXED

Hole drilled with cable tools
from 3719-23½'

PLUGGING
FILE SEC. 31-128-9W
BOOK PAGE 11 LINE 38

263' of 10"
3718' 5"

15-155-02142-0000
SCHWEIZER No 2 Sec 31, NW 31-22-9W Reno County, Kansas.
Hinkle Oil Company & N. Appleman Company
Contractor J. B. Hinkle.
Commenced 3-12-42 Completed 3-31-42

Cementing record.
263 feet of 10" cemented with 185 sax cement.
2718' " 5" " " 60 sax cement.
no perforations.

0	263	Surface
263	330	Red Rock
330	355	Anhydrite
355	1250	Shale
1250	1465	Broken line
1465	1675	Lime
1675	1700	Shale
1700	1745	Lime
1745	1800	Sandy Lime
1800	2165	Broken Line
2165	2205	Shale
2205	2360	Shale and shells
2360	2425	Shale
2425	2625	Lime and shale
2625	2660	Lime
2660	2712	Shale
2712	2985	Lime
2985	3005	Broken Line
3005	3040	Lime
3040	3054	Shale
3054	3142	Broken lime and shale
3142	3205	Shale and shells
Top of K. C. Line		3203
3205	3252	Lime
3252	3282	Shale
3282	3330	Broken line
3330	3528	Lime
Top of Kenderhook		3507
3528	3540	Shale
3540	3590	Lime
3590	3670	Shale
3670	3675	Sandy lime
3675	3699	Shale
3699	3719	Lime
Top of Mianer		3674
Top of Viola		3699
Top of Dolomite		3718
Hole drilled with cable tools		
to		3723 1/2

JUN 19 1950
STATE CORPORATION
COMMISSION
KANSAS

State of Kansas }
County of Sedgwick } S.S.

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept at said well.

J. B. Hinkle

Subscribed and sworn to before me this 20th. day of April, 1942.

PLUGGING
FILE SEC-31 T-22 R-9W
BOOK PAGE-11 LINE-38

Muril A. Nystrom
N. P.

My commission expires 1-17-46