


15-155-02143-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Reno County. Sec. 31 Twp. 22 Rge. 9 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SWc NE 1/4 NW 1/4  
Lease Owner Hinkle Oil Company  
Lease Name Schweizer Well No. 3  
Office Address 914 Union Natl Bank Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19...  
Application for plugging filed 19...  
Application for plugging approved 19...  
Plugging commenced January 31, 1950 19...  
Plugging completed February 5, 1950 19...  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. Durkee  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	254	none
				5 1/2"	3710	3098'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Run 6 sacks of cement at 3714'.  
Mudded hole to 245'. Set rock bridge and run 20 sacks of cement.  
Mudded hole to top. Run 5 sacks of cement. Well Completed

FFB 1-1-1950 2-11-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hinkle Oil Company  
Address 914 Union Natl Bank Bldg  
Wichita, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, SS.

\_\_\_\_\_(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) J B Hinkle  
914 Union Natl Bank Bldg  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10 day of February, 19 50

Murrel A. Upton  
Notary Public.

My commission expires Jan 17, 1954

22-7377-8 4-49-10M



Casing record.  
 10" 254'  
 5" 3710'

Schroeder No. 3.

Dono County, Kansas.  
 SWS No. 1124 1124 11-22-9

Hinkle Oil Company and H. Appleman Company  
 Contractor J. B. Hinkle.

Commenced July 2, 1942 Completed July 17, 1942

0	254	Surface
254	510	Red Rock
510	1420	Shale and shales
1420	1780	Lime
1780	1840	Sandy Lime
1840	2005	Lime
2005	2105	Broken Lime
2105	2165	Lime
2165	2220	Shale
2220	2260	Lime
2260	2303	Shale
2303	2376	Broken Lime
2376	2595	Shale
2595	2650	Lime
2650	2705	Broken Lime
2705	3045	Lime
3045	3227	Broken Lime
3227	3526	Lime
3526	3580	Cherty Lime
3580	3713	Lime

Bottom of Rotary hole.

Top of Viola Lime 3683 Rotary table = -1953  
 Top of Dolomite 3712 = -1972

Hole drilled to 3715; corrected derrick floor measurements.

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept at said well.

J. B. Hinkle

State of Kansas }  
 County of Sedgewick } ss

Subscribed and sworn to before me this 29th. day of July, 1942 by  
 J. B. Hinkle.

Muriel A. Upton

My commission expires 1-17-46

RECORDED

FEB 11 1950

2-11-50

STATION

PLUGGING  
 FILE NO. 317-2219w  
 SICK FILE 137 FILE 33