


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Reno County, Sec. 1 Twp. 22S Rge. 10W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NW SE

Lease Owner Shileds Oil Producers, Inc.  
Lease Name Brown "A" #2 Well No. 2  
Office Address P. O. Box 709, Russell, Kansas 67665  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Dry Hole  
Date Well completed April 15, 1979 19  
Application for plugging filed April 15, 1979 19  
Application for plugging approved April 15, 1979 19  
Plugging commenced 11:45 AM, April 15, 1979 19  
Plugging completed 1:30 PM, April 15, 1979 19  
Reason for abandonment of well or producing formation

Dry Hole  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 3165'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	218'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Heavy mud to 500' with 40 sacks through  
drill pipe, heavy mud to 210' with 25 sacks  
thru drill pipe; heavy mud to 40' with solid  
bridge and 1/2 sack hulls at 40'. 10 sacks  
to surface and 25 sacks in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stering Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
Bernard Laudermilk (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Bernard Laudermilk  
STERLING DRILLING COMPANY  
Bernard Laudermilk, President  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 1979

My commission expires



Charles M. Hall, Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
4-19-79  
APR 19 1979

CONSERVATION DIVISION  
Wichita, Kansas

15-155-20590-0000

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- BROWN A-2  
Located: C NW SE, Section 1-22S-10W, Reno County, Kansas

OWNER: Shields Oil Producers, Inc.  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 11, 1979  
COMPLETED: April 15, 1979

TOTAL DEPTH: 3165'

LOG

CASING RECORD

0 - 223	Sand, Clay and Red Bed	Ran 5 joints of 5/8" casing, 207' set at 218' K.B. Cemented with 225 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 3:30 PM, 4-11-79, by Sun Cementing Co.
223 - 1295	Shale and Shells	
1295 - 2650	Shale and Lime	
2650 - 2960	Lime	
2960 - 3135	Lime and Shale	
3135 - 3165	Lime	Plugged.

4-19-79  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 19 1979  
 CONSERVATION DIVISION  
 Wichita, Kansas