


Give All Information Completely
 Make Required Affidavit
 Map or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

WELL PLUGGING RECORD

EDWARDS County, Sec. 1 Twp. 24S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines. CS-SI-N
 Lease Owner BOB WHITE
 Lease Name REAVES Well No. 1
 Office Address 714 UNION CENTER, WICHITA, KANSAS
 Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
 Date well completed JULY 31, 19 62
 Application for plugging filed JULY 31, 19 62
 Application for plugging approved JULY 31, 19 62
 Plugging commenced JULY 31, 19 62
 Plugging completed JULY 31, 19 62
 Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT, 222 S. MAIN, ST. JOHN, KANSAS
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4038 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>CLAY, SAND & SHALE</u>	<u>SURF. CASING</u>	<u>0-</u>	<u>230'</u>	<u>8-5/8"</u>	<u>230'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE: Filled hole with heavy mud
4038' up to 200'. Bridged using 1/4 sk. balls,
Halliburton Plug, 20 sx. cement through drill
pipe.
Filled hole with mud to 35', bridged with 1/4 sk.
balls, Halliburton Plug, 10 sx. cement to cellar
zero. 2 sx. cement in rat hole.

Job Completed: 8:45 a.m. Rig released 9 a.m. 7-31-62.

RECEIVED
 STATE CORPORATION COMMISSION
8-2-62
 AUG 2 1962

CONSERVATION DIVISION

Name of Plugging Contractor SIERRA PETROLEUM CO., INC. (If additional description is necessary, use BACK of this sheet) Wichita, Kansas
 Address BOX 232, RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. HONAKER, DRILLING SUPERINTENDENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRLG. SUPT.
BOX 232, RUSSELL, KANSAS
 (Address)

SUBSCRIBED AND SWORN TO before me this 1ST day of AUGUST, 19 62

My commission expires 10-17-63 Gray Dutz Notary Public.



ROBERT F. WHITE - Operator

SIERRA PETROLEUM CO., INC - Contractor

REAVES #1
CS $\frac{1}{2}$ -SW-NW
Sec. 1-24S-16W
Edwards County, Kansas

T. D.: 4038'

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1962

CONSERVATION DIVISION
Wichita, Kansas

Commenced: 7-19-62
Completed: 7-31-62

Casing:

8-5/8" Set at 230'

Cement:

with 210 sk. cement

FORMATION

DEPTH

Clay & Sand	90
Shale	450
Sand	510
Red Bed	965
Anhydrite	995
Shale & Shells	1785
Shale & Lime	3327
Lime	3495
Lime & Shale	3610
Lime	3964
Lime & Shale	4038

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker
Drilling Superintendent

Subscribed and sworn to before me this 1st day of August, 1962.

Erroy Dietz
Notary Public

My Commission Expires: 10-17-63