


WELL PLUGGING RECORD

All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Edwards County. Sec. 1 Twp. 24S Rge. 16 XK (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Wilco Oil, Inc.
Lease Name Bright Well No. 1
Office Address Box 13528, Phoenix, Arizona
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May 30 19 48
Application for plugging filed September 4 19 63
Application for plugging approved 19
Plugging commenced November 4 19 63
Plugging completed November 9 19 63
Reason for abandonment of well or producing formation Uneconomic

If a producing well is abandoned, date of last production November 5 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Lansing-Kansas City Depth to top 3597 Bottom 3883 Total Depth of Well 3980 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City	Gas, oil, wtr.	3597	3883	8 5/8	360	-
				5 1/2	3982	2397.19

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 3600' 5 sax cement to 3570'
Mud from 3570 to 275' Rock from 275 to 265'
6 sax cement 265 to 250'
Bailed out water 19 sax cement 250 to 210'
Mud 210 to 30' Rock and 10 sax cement 30' to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
12-10-63
DEC 10 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith
Address Box 156, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Daniels
James R. Daniels
308 Schweiter Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 63

My commission expires November 18, 1966

Colleen Chapple
Colleen Chapple Notary Public.

DRILLING LOG

Operator: Max Cohen (Now Wilco Oil, Inc.)
Contractor: Brunson Drilling Company
Commenced: 4/15/48
Completed: 5/30/48
Elevation: 2056 R.B.

Well: Bright No. 1
Location: NW NW SW Sec. 1-24S-16W
Edwards County, Kansas
Casing: 8 5/8" at 360'
5 1/2" at 3982' w/175 sx.

Figures indicate bottom of formations:

Formation Tops

Sand	140'
Clay & Sand	210'
Shale & Shells	325'
Red Shale	460'
Sand	510'
Shale & Shells	968'
Anhydrite	1013'
Shale & Shells	1320'
Sandy Shale	1640'
Shale	1840'
Shale & Lime	2660'
Shale	2920'
Lime & Shale	3145'
Lime	3458'
Shale (Heebner)	3463'
Lime	3491'
Sand & Shale	3595'
Lime	3885'
Lime & Shale	3954'
Granite	3980'
Total Depth	3980'

Anhydrite	968'
Topeka	3145'
Heebner	3458'
Br. Lime	3586'
Lansing K.C.	3597'
Base K.C.	3883'
Wea. Pre Cambrian	3954'
Pre Cambrian	3971'
Total Depth	3980'

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1963

CONSERVATION DIVISION
Wichita, Kansas

The above log is based on information provided by the drilling contractor; on the report of the geologist employed to supervise drilling operations; and upon analysis of a radioactivity log ran on subject well. To the best knowledge of the undersigned this represents a true and correct log of the formations penetrated in the drilling of the Bright No. 1 Well.

WILCO OIL, INC.

By James R. Daniels
James R. Daniels
Geological Engineer

State of Kansas)
) SS
County of Sedgwick)

Subscribed and sworn to before me, a notary public, in and for the county and state on this 4th day of September, 1963.

My commission expires 11-18-66

Colleen Chapple
Colleen Chapple Notary Public